MYSORE DIVISION.

Dated 12th March 1917.

Notice is hereby given that sealed tenders will be received at the office of the President, City Municipal Council, Mysore, up to end of March 1917, for extending Devaraj Market Blocks A. and F. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1917.

2. The plans, detailed estimates and conditions may be seen at the Municipal Engineer's Office at Town Hall, Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees five hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extending Blocks A. and F. of Devaraj Market" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Municipal Council, Mysore, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Municipal Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

An approximate estimate of the quantities required for the work.

Details of work	Per	Quantity	Remarks
Earthwork excavating foundation and filling in basement	C. yd.	521	
Concrete filling in foundation	C. ft.	5,671	
Burnt brick in mortar foundation and basement	,,	8,300	
Do superstructure	,,	17,869	
Do plain archwork	,,	32	
Do foliated archwork	,,	50	
Cut stone in mortar, bases of pillars nicely dressed	No.	18	
Burnt stone slabs dressed 6" thick	Sq. ft.	2,503	
Teakwood panelled doors with hinges, locks and bolts, etc.	,,	2,319	
Do glazed ventilators rectangulars do	,,	368	
Do work wrought and put up, big scantlings	C. ft.	466·34	
Do do small scantlings	,,	1022·41	
Roofing with pukka terrace 9" thick, complete	Sq.	77·83	
Plastering with chunam	,,	292	
White and colour washing	,,	292	
Flooring with Cuddapah slabs over 3" concrete and cement pointing	,,	55	
Silicate painting	,,	53·74	
Dental cornice	R. ft.	64	
Cornice 9" thick ornamental	,,	555	
Do plain	,,	60	
Do 4½" thick for parapet	,,	592	
Ornamental parapet wall 2 ft. high	,,	180	
Do pediment over parapet wall	No.	2	
Do teakwood eave board 10" wide and 1" thick	R. ft.	180	
Do gate, complete	No.	2	
Masonry finials, large	,,	32	
Do small	,,	38	
Ornamental work for pedestals	,,	22	

T. G. LAKSHMANA RAO,
President.

KADUR DIVISION.

Dated 13th March 1917.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 15th April 1917, for constructing Police Lines at Sollebyle, Koppa Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1918.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A.M. and 5 P.M. on Office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 (Two hundred) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Police Lines at Sollebyle, Koppa Taluk," in default of which, tenders will be rejected.